

RFI Report - Addendum 02

1132047401  
 ASU Hickory - Phase IIA  
 Prepared on 04/29/2024  
 Revised on 04/30/2024

Status	RFI ID	Subject	Question	Answer	Closed
Closed	01	Construction Access	Is there a service elevator available during construction.	See the appendix to Addendum 01 - A service elevator is available with access from the existing loading dock and South Parking Lot - Note that occupied student areas will remain closed to construction unless after hours, during non-class time or otherwise coordinated with Owner. Half of the south parking lot will be available for lay down area	4/29/2024
Closed	02	Building Shut Down	Will the building be occupied during construction.	The Building is to be considered Occupied at Level(s) 1 and 5 during normal business hours.	4/29/2024
Closed	03	Lab Casework	Is the gc to provide the casework for the General Lab?	All Lab Casework, plumbing fixtures and equipment within the casework, and emergency shower eye wash to be provided by Owner Provided GC Installed	4/29/2024
Closed	04	Modified Submittal Review Time	Will the owner and design team consider a modified review time from the standard 10 days for the compressed schedule of this project?	Yes, a modified RFI and Submittal Review time will be considered and agreed upon prior to the beginning of construction.	4/29/2024
Closed	05	Door Frame	Are Knock-Down Door Frames, welded in place acceptable?	Yes, Knock-Down Frames, welded in place are acceptable.	4/29/2024
Closed	06	Division 27	Division 27 specifications are not provided in the spec book - is the owner providing all division 27 communications cabling for data outlets?	Yes, This is provided by owner. The GC is to install conduit, as specified, in all 'exposed' ceiling areas and wall.	4/29/2024
Closed	07	Existing Wall Framin	Is the existing wall framing and drywall required to go to deck in the open area with no ceiling?	Yes, if there is an exposed area not indicated by keynote 1 on the floor plan, new drywall is to be installed at finished side of existing wall at occupied space to underside of existing structure above. To be finished per the Phase IIA Finish Plan	4/29/2024
Closed	08	Lab Casework Manufacturer	Can you please provide the casework manufacturer / supplier name and contact information?	The basis of design casework is by Nycorn, Inc. Contact: Casey Gay, Account Manager, CGAY@NYCOMINC.COM	4/30/2024
Closed	09	Roof Penetrations	A. Are the Mechanical roof penetrations new or existing? B. Are there other penetrations as well? B.1 If so, does it might make sense for the owner to require all bidders to use Davco so as not to void their warranty.	A. These are new roof penetrations B. There are 2 Duct and 2 Piping penetrations in the Mehcanical Scope B.1. The Roof Warranty is to be maintained.	4/30/2024
Closed	10	Floor to Floor Height	Please confirm heigh from floor to under side of deck above. It scales 11'8" on drawings, please confirm accuracy.	The existing As-Built Documents list dimension from the Level 2 Top of Slab to the Level 3 Top of Slab as +/- 12'-0"	4/30/2024
Closed	11	APC Ceiling Tile	Please clarify the building standard tiles for APC1, APC2, and APC4.	Basis of design for pricing is as follows: Final coordination to be determined with owner review of existing building finishes. APC-1: Typical Classroom areas: Armstrong Ultima High NRC: 15/16" Beveled Tegular: 24x24x7/8 APC-2: Alternate 2 Restroom Renovation:tArmstrong Ultima High NRC: 15/16" Beveled Tegular: Wipeable Surface: 24x24x7/8 APC-4: Corridor Ceiling: Armstrong Ultima High NRC: 15/16" Beveled Tegular: 24x72x7/8	4/30/2024
Closed	12	Turf Arbor Tile	FC1 Turf Arbor is listed on the finish legend. However, it is not shown on the RCP. Please clarify the designated area and design intent for this material.	This is to be omitted in this project Phase	4/30/2024
Closed	13	PFT Base	What is the desired size for PFT1 to be cut down to for tile base? 6" x 24"? 4" x 24"?	6" Cut Tile size is preferred.	4/30/2024
Closed	14	Rubber Base	Please confirm that RB2 is not used.	RB2 is to be used in the Cyber Lab RB-3 is to be omitted	4/30/2024

Status	RFI ID	Subject	Question	Answer	Closed
Closed	15	Cyber Lab Rubber Base	Cyber Lab 2221 calls for RB3. What is the desired color for RB3. Only RB2 is to be used in the Cyber Lab RB-3 is to be omitted RB1 and 2 are listed on the Finish Legend.		4/30/2024
Closed	16	ALT 1 Corridor Carpet	Please confirm that Corridor 2210 on Alternate 1 is to receive CPT0. Carpet to be CPT-0 The finish plan shows a 9" x 36" hashing.		4/30/2024
Closed	17	FRP Class	Will the class of the FRP be Class A or Class C. Please Clarify	Class A is preferred	4/30/2024

**Total RFIs: 17**